

## CONSTRUCTION NOTES

CONSTRUCT


1. 4" PCC SIDEWALK PER CITY OF BEVERLY HILLS STD. PLAN BH 105 AND BH 104. SAWCUT AND JOIN SIDEWALK AT NEAREST JOINT.

## LEGEND

CONCRETE

## NOTES:

- 1. LOCATION OF EXISTING UTILITIES ARE APPROXIMATE AND DEPTH ARE UNKNOWN. CONTRACTER SHALL VERIFY THE LOCATION AND DEPTH OF ALL UTILITIES PRIOR TO THE START OF EXCAVATION AND PROTECT IN PLACE ALL UTILITIES ENCOUNTERED. DAMAGED UTILITY FACILITIES SHALL BE REPAIRED AT NO ADDITIONAL COST.
- 2. CONTRACTOR SHALL BACKFILL AND PLACE SOD IN TURF AREAS DAMAGED BY THE CONSTRUCTION.



NOT TO SCALE



PUBLIC WORKS DEPARTMENT

345 FOOTHILL RD BEVERLY HILLS, CALIFORNIA 90210 310 285-2514 FAX 310.278-1338 www.beverlyhills.org

SCALES AS SHOWN			SIDEWALK — N SANTA MONICA BLVD	
F.B. NO. PAGE TO		0	BETWEEN WILSHIRE AND WALDEN	
DESIGNED	DATE		SUBMITTED DATE	
DRAWN	DATE		SUBMITTED	
CHECKED	DATE		APPROVED DATE	
			ALTROVED_	
			JOB NO. 2202	DRWG.
			SHEET NO. 1 OF 1 SHEETS	NO7505
			CITY OF BEVERLY HILLS, CALIFORNIA	
DATE	REVISION	BY	PUBLIC WORKS DEPARTMENT	ENGINEERING DIVISION